



NEPTUNE CAMPUS, NEAR ATLANTIS HEIGHTS, DR.VIKRAM SARABHAI MARG, VADIWADI, VADODARA,GUJARAT, 390007

Ph.No. : 0265-2350630/39 Website : www.neptunerealtygroup.com

WORK ORDER

WO No.	392	SHIP TO:	
WO Date:	28/12/2023	NEPTUNE REALTY PVT. LTD.	
Contractor Name	TransCube Engineers Pvt Ltd	GREENWOOD ASPIRE EXP	
Address:	FF-61, Shiddheswar Harbour,Waghodiya Road, Vadodara-390010, Gujarat-India.	Neptune Campus, Sarabhai Road, Vadodara	
Contact No		WO Title	
PAN :	AAJCT8508L		
GST :	24AAJCT8508L1ZW	GST No:	24AAACN9837D1ZI Gujarat

We have pleasure in placing with you our Work order for the following contract kindly execute the work as per the instruction given by our site incharge.

Sr.No	Item Description	Qty	Unit	Rate Rs.	Amount	GST %
1	INFRA ELECTRIC WORK 100MM DIA 3 MTR 13MM THK CENTRIFUGAL CAST IRON PIPE	16.00	NOS	850.00	13600.00	18 %
2	INFRA ELECTRIC WORK CHARGES FOR 75MM DIA, 2.9/3 MTR CENTRIFUGAL CAST IRON PIPE	62.00	NOS	850.00	52700.00	18 %
3	INFRA ELECTRIC WORK CHARGES FOR 8 SWG GI EARTH WIRE	780.00	RMT	15.00	11700.00	18 %
4	INFRA ELECTRIC WORK INSTALLATION CHARGES FOR 250 KVA TRANSFORMER (NOS)	2.00	NOS	2500.00	5000.00	18 %
5	INFRA ELECTRIC WORK INSTALLATION CHARGES FOR 500 KVA TRANSFORMER (NOS)	6.00	NOS	2500.00	15000.00	18 %
6	INFRA ELECTRIC WORK INSTALLATION CHARGES FOR EARTH TERMINAL STATION (NOS)	19.00	NOS	100.00	1900.00	18 %
7	INFRA ELECTRIC WORK LABOR FOR 25X3MM COPPER FLAT (RMT)	1,560.00	RMT	35.00	54600.00	18 %
8	INFRA ELECTRIC WORK LABOR FOR DWC 180/150 MM DIA PIPE WITH COUPLER (RMT)	435.00	RMT	20.00	8700.00	18 %
9	INFRA ELECTRIC WORK LABOR FOR DWC 90/75 MM DIA PIPE WITH COUPLER (RMT)	890.00	RMT	20.00	17800.00	18 %
10	INFRA ELECTRIC WORK LABOR FOR EXCAVATION (CMT)	369.00	CMT	90.00	33210.00	18 %
11	INFRA ELECTRIC WORK CHARGES FOR 1 C x 300 SQMM ALU. ARMOURED XLPE LT CABLE (RMT)	3,670.00	RMT	36.00	132120.00	18 %
12	INFRA ELECTRIC WORK CHARGES FOR 1 C x 400 SQMM ALU. ARMOURED XLPE LT CABLE (RMT)	132.00	RMT	45.00	5940.00	18 %

We have pleasure in placing with you our Work order for the following contract kindly execute the work as per the instruction given by our site incharge.

13	INFRA ELECTRIC WORK CHARGES FOR 3 C x 240 SQMM ALU. ARMoured XLPE HT CABLE (RMT)	440.00	RMT	90.00	39600.00	18	%
14	INFRA ELECTRIC WORK CHARGES FOR 3 C x 70 SQMM ALU. ARMoured XLPE HT CABLE (RMT)	216.00	RMT	70.00	15120.00	18	%
15	INFRA ELECTRIC WORK CHARGES FOR 3.5Cx 120 SQMM ALU. ARMoured XLPE LT CABLE (RMT)	198.00	RMT	50.00	9900.00	18	%
16	INFRA ELECTRIC WORK LABOR FOR 25MM PVC PIPE (MTR)	470.00	RMT	15.00	7050.00	18	%
17	INFRA ELECTRIC WORK CHARGES FOR 3.5C x 25 SQMM ALU. ARMoured XLPE LT CABLE (RMT)	170.00	RMT	35.00	5950.00	18	%
18	INFRA ELECTRIC WORK CHARGES FOR 1C x 300 SQMM XLPE LT CABLE TERMINATION (NOS)	240.00	NOS	350.00	84000.00	18	%
19	INFRA ELECTRIC WORK CHARGES FOR 1C x 400 SQMM XLPE LT CABLE TERMINATION (NOS)	10.00	NOS	490.00	4900.00	18	%
20	INFRA ELECTRIC WORK CHARGES FOR 3.5Cx 120 SQMM XLPE LT CABLE TERMINATION (NOS)	4.00	NOS	500.00	2000.00	18	%
21	INFRA ELECTRIC WORK CHARGES FOR 3.5Cx 25 SQMM XLPE LT CABLE TERMINATION (NOS)	6.00	NOS	370.00	2220.00	18	%
22	INFRA ELECTRIC WORK CHARGES FOR 3C x 240 SQMM XLPE HT CABLE TERMINATION (NOS)	28.00	NOS	2500.00	70000.00	18	%
23	INFRA ELECTRIC WORK CHARGES FOR 3C x 70 SQMM XLPE HT CABLE TERMINATION (NOS)	8.00	NOS	2000.00	16000.00	18	%
24	INFRA ELECTRIC WORK CHARGES FOR 400 x 50/75 x 1.6 GI LADDER TYPE CABLE TRAY	25.00	RMT	130.00	3250.00	18	%
25	INFRA ELECTRIC WORK CHARGES FOR 600 x 50/75 x 1.6 GI LADDER TYPE CABLE TRAY	252.00	RMT	155.00	39060.00	18	%
26	INFRA ELECTRIC WORK CHARGES FOR 200 x 50/75 x 1.6 GI LADDER TYPE CABLE TRAY	155.00	RMT	120.00	18600.00	18	%
27	INFRA ELECTRIC WORK CHARGES FOR 300 x 50/75 x 1.6 GI LADDER TYPE CABLE TRAY	25.00	RMT	130.00	3250.00	18	%
28	INFRA ELECTRIC WORK CHARGES FOR LOAD BREAK SWITCH (NOS)	2.00	NOS	5500.00	11000.00	18	%
29	INFRA ELECTRIC WORK CHARGES FOR M.S. STRUCTURAL WORK (KG)	2,380.95	KG	25.00	59523.75	18	%
30	INFRA ELECTRIC WORK CHARGES FOR RMU (NOS)	1.00	NOS	6500.00	6500.00	18	%
31	INFRA ELECTRIC WORK LABOUR FOR DB FITTING (NOS)	1.00	NOS	2500.00	2500.00	18	%

We have pleasure in placing with you our Work order for the following contract kindly execute the work as per the instruction given by our site incharge.

32	INFRA ELECTRIC WORK							
	LABOR FOR MAIN DB (NOS)	2.00	NOS	2500.00	5000.00	18	%	
33	INFRA ELECTRIC WORK							
	LABOUR FOR DB FITTING (NOS)	3.00	NOS	1550.00	4650.00	18	%	
						Contract Amount (A)		762343.75
						Total GST (B)		137221.88
						Total (A + B)		899565.63

Terms & Conditions

Payment AS PER ATTACHEMENT

Other Conditions ALL THE TERMS AND CONDITION AS PER THE ATTACHEMENT.

SAFETY TERMS

- 1) Work Compensation (WC) Policy is a must for every contractor.
- 2) Required all their laborers Aadhar card copy and Passport size Photo.
- 3) All PPES in Contractor Scope.
- 4) TPI (Third Party Inspection) Certificate must for their Machineries which they install on our site.
- 5) Every Quarterly they must submit a service report of their respective machines to the site incharge.
- 6) Contractor has to maintain enough lighting during night work at site.
- 7) Debit Note Policy will be applicable if the contractor failed to maintain the safety norms

* All responsibilities of goods during transportation and unloading at site by supplier and vendors.

* Please submit your Bill/invoice along with delivery challan and PO copy in favour of Neptune Realty Pvt. Ltd.

At project site office officialy.

* Billing amount should not exceed the rate and total value mentioned in this WO.

* Failure to comply with specification, terms and conditions of this order or accepted delivery. schedule shall be sufficient grounds for cancellation of order by purchase with out being liable.

For NEPTUNE REALTY PVT. LTD.

Authorized Signatory
