



NEPTUNE CAMPUS, NEAR ATLANTIS HEIGHTS, DR.VIKRAM SARABHAI MARG, VADIWADI, VADODARA,GUJARAT, 390007

Ph.No. : 0265-2350630/39 Website : www.neptunerealtygroup.com

WORK ORDER

| | | | |
|------------------------|--|--|----------------|
| WO No. | 417 | SHIP TO: | |
| WO Date: | 04/04/2024 | NEPTUNE REALTY PVT. LTD. | |
| Contractor Name | Sahas Roads & Infrastructure | GREENWOOD ASPIRE EXP | |
| Address: | Pvt.Ltd GF-1&2/ML, Meghdhanush Complex,Race Course Circle,, Vadodara 390007, India.MO:919879531402 | Neptune Campus, Sarabhai Road, Vadodara | |
| Contact No | | WO Title | |
| PAN : | | | |
| GST : | | GST No: 24AAACN9837D1ZI | Gujarat |

We have pleasure in placing with you our Work order for the following contract kindly execute the work as per the instruction given by our site incharge.

| Sr.No | Item Description | Qty | Unit | Rate Rs. | Amount | GST % |
|-------------|--|----------|------|----------|----------|-------|
| 1 | TOWER A GROUND FLOOR TRIMIX WORK LABOR FOR EXCAVATION (SQFT) | 3,619.98 | SQFT | 6.00 | 21719.88 | 18 % |
| 2 | TOWER A GROUND FLOOR TRIMIX WORK LABOR FOR GROOVE CUTTING WITH BITUMEN FILLING (SQFT) | 3,619.98 | SQFT | 1.75 | 6334.97 | 18 % |
| 3 | TOWER A GROUND FLOOR TRIMIX WORK LABOR FOR PCC (SQFT) | 3,619.98 | SQFT | 4.00 | 14479.92 | 18 % |
| 4 | TOWER A GROUND FLOOR TRIMIX WORK LABOR FOR STEEL BINDING (SQFT) | 3,619.98 | SQFT | 2.10 | 7601.96 | 18 % |
| 5 | TOWER A GROUND FLOOR TRIMIX WORK LABOUR FOR QUARRY DUST (SQFT) | 3,619.98 | SQFT | 2.25 | 8144.96 | 18 % |
| 6 | TOWER A GROUND FLOOR TRIMIX WORK LABOUR FOR TRIMIX (SQFT) | 3,619.98 | SQFT | 9.00 | 32579.82 | 18 % |
| 7 | TOWER A GROUND FLOOR TRIMIX WORK LABOR FOR GROOVE CUTTING WITH BITUMEN FILLING (SQFT) | 2,000.00 | SQFT | 1.75 | 3500.00 | 18 % |
| 8 | TOWER A GROUND FLOOR TRIMIX WORK LABOR FOR STEEL BINDING (SQFT) | 2,000.00 | SQFT | 2.10 | 4200.00 | 18 % |
| 9 | TOWER A GROUND FLOOR TRIMIX WORK LABOUR FOR TRIMIX (SQFT) | 2,000.00 | SQFT | 9.00 | 18000.00 | 18 % |
| 10 | TOWER A GROUND FLOOR ROAD WORK LABOUR FOR QUARRY DUST (SQFT) | 4,547.12 | SQFT | 2.25 | 10231.02 | 18 % |
| Spc. | As per Latest new revised duly signed new drawings Add WMM & Trimix Quantity in WO No. 417 Sahas Road & Infrastructure | | | | | |
| 11 | TOWER A GROUND FLOOR ROAD WORK LABOUR FOR TRIMIX (SQFT) | 4,547.12 | SQFT | 9.00 | 40924.08 | 18 % |
| Spc. | As per Latest new revised duly signed new drawings Add WMM & Trimix Quantity in WO No. 417 Sahas Road & Infrastructure | | | | | |

We have pleasure in placing with you our Work order for the following contract kindly execute the work as per the instruction given by our site incharge.

| | | | | | | | |
|--|--|-----------|------|-------|-----------|----|---|
| 12 | TOWER A GROUND FLOOR ROAD WORK LABOUR FOR WMM (SQFT) | 9,094.24 | SQFT | 18.00 | 163696.32 | 18 | % |
| Spc. As per Latest new revised duly signed new drawings Add WMM & Trimix Quantity in WO No. 417 Sahas Road & Infrastructure | | | | | | | |
| 13 | TOWER A GROUND FLOOR ROAD WORK LABOUR FOR WMM (SQFT) | 3,000.00 | SQFT | 18.00 | 54000.00 | 18 | % |
| 14 | TOWER A GROUND FLOOR ROAD WORK LABOR FOR EXCAVATION (SQFT) | 4,547.12 | SQFT | 6.00 | 27282.72 | 18 | % |
| 15 | TOWER A GROUND FLOOR ROAD WORK LABOR FOR GROOVE CUTTING WITH BITUMEN FILLING (SQFT) | 4,547.12 | SQFT | 1.75 | 7957.46 | 18 | % |
| 16 | TOWER A GROUND FLOOR ROAD WORK LABOR FOR PCC (SQFT) | 4,547.12 | SQFT | 4.00 | 18188.48 | 18 | % |
| 17 | TOWER A GROUND FLOOR ROAD WORK LABOR FOR STEEL BINDING (SQFT) | 4,547.12 | SQFT | 2.10 | 9548.95 | 18 | % |
| 18 | TOWER B GROUND FLOOR TRIMIX WORK LABOUR FOR TRIMIX (SQFT) | 1,308.32 | SQFT | 9.00 | 11774.88 | 18 | % |
| 19 | TOWER B GROUND FLOOR TRIMIX WORK LABOUR FOR QUARRY DUST (SQFT) | 1,308.32 | SQFT | 2.25 | 2943.72 | 18 | % |
| 20 | TOWER B GROUND FLOOR TRIMIX WORK LABOR FOR STEEL BINDING (SQFT) | 1,308.32 | SQFT | 2.10 | 2747.47 | 18 | % |
| 21 | TOWER B GROUND FLOOR TRIMIX WORK LABOR FOR PCC (SQFT) | 1,308.32 | SQFT | 4.00 | 5233.28 | 18 | % |
| 22 | TOWER B GROUND FLOOR TRIMIX WORK LABOR FOR GROOVE CUTTING WITH BITUMEN FILLING (SQFT) | 1,308.32 | SQFT | 1.75 | 2289.56 | 18 | % |
| 23 | TOWER B GROUND FLOOR TRIMIX WORK LABOR FOR EXCAVATION (SQFT) | 1,308.32 | SQFT | 6.00 | 7849.92 | 18 | % |
| 24 | TOWER B GROUND FLOOR TRIMIX WORK LABOUR FOR TRIMIX (SQFT) | 2,760.00 | SQFT | 9.00 | 24840.00 | 18 | % |
| 25 | TOWER B GROUND FLOOR TRIMIX WORK LABOR FOR STEEL BINDING (SQFT) | 2,760.00 | SQFT | 2.10 | 5796.00 | 18 | % |
| 26 | TOWER B GROUND FLOOR TRIMIX WORK LABOR FOR GROOVE CUTTING WITH BITUMEN FILLING (SQFT) | 2,760.00 | SQFT | 1.75 | 4830.00 | 18 | % |
| 27 | TOWER B GROUND FLOOR ROAD WORK LABOUR FOR WMM (SQFT) | 11,194.82 | SQFT | 18.00 | 201506.76 | 18 | % |
| 28 | TOWER B GROUND FLOOR ROAD WORK LABOUR FOR TRIMIX (SQFT) | 5,597.41 | SQFT | 9.00 | 50376.69 | 18 | % |
| 29 | TOWER B GROUND FLOOR ROAD WORK LABOUR FOR QUARRY DUST (SQFT) | 5,597.41 | SQFT | 2.25 | 12594.17 | 18 | % |
| 30 | TOWER B GROUND FLOOR ROAD WORK LABOR FOR STEEL BINDING (SQFT) | 5,597.41 | SQFT | 2.10 | 11754.56 | 18 | % |
| 31 | TOWER B GROUND FLOOR ROAD WORK LABOR FOR PCC (SQFT) | 5,597.41 | SQFT | 4.00 | 22389.64 | 18 | % |
| 32 | TOWER B GROUND FLOOR ROAD WORK LABOR FOR GROOVE CUTTING WITH BITUMEN FILLING (SQFT) | 5,597.41 | SQFT | 1.75 | 9795.47 | 18 | % |

We have pleasure in placing with you our Work order for the following contract kindly execute the work as per the instruction given by our site incharge.

| | | | | | | | |
|----|---|----------|------|-------|-----------|----|---|
| 33 | TOWER B GROUND FLOOR ROAD WORK LABOR FOR EXCAVATION (SQFT) | 5,597.41 | SQFT | 6.00 | 33584.46 | 18 | % |
| 34 | TOWER C GROUND FLOOR TRIMIX WORK LABOUR FOR QUARRY DUST (SQFT) | 4,100.86 | SQFT | 2.25 | 9226.94 | 18 | % |
| 35 | TOWER C GROUND FLOOR TRIMIX WORK LABOUR FOR TRIMIX (SQFT) | 4,100.86 | SQFT | 9.00 | 36907.74 | 18 | % |
| 36 | TOWER C GROUND FLOOR TRIMIX WORK LABOR FOR EXCAVATION (SQFT) | 4,100.86 | SQFT | 6.00 | 24605.16 | 18 | % |
| 37 | TOWER C GROUND FLOOR TRIMIX WORK LABOR FOR GROOVE CUTTING WITH BITUMEN FILLING (SQFT) | 4,100.86 | SQFT | 1.75 | 7176.51 | 18 | % |
| 38 | TOWER C GROUND FLOOR TRIMIX WORK LABOR FOR PCC (SQFT) | 4,100.86 | SQFT | 4.00 | 16403.44 | 18 | % |
| 39 | TOWER C GROUND FLOOR TRIMIX WORK LABOR FOR STEEL BINDING (SQFT) | 4,100.86 | SQFT | 2.10 | 8611.81 | 18 | % |
| 40 | TOWER C GROUND FLOOR TRIMIX WORK LABOR FOR GROOVE CUTTING WITH BITUMEN FILLING (SQFT) | 2,000.00 | SQFT | 1.75 | 3500.00 | 18 | % |
| 41 | TOWER C GROUND FLOOR TRIMIX WORK LABOR FOR STEEL BINDING (SQFT) | 2,000.00 | SQFT | 2.10 | 4200.00 | 18 | % |
| 42 | TOWER C GROUND FLOOR TRIMIX WORK LABOUR FOR TRIMIX (SQFT) | 2,000.00 | SQFT | 9.00 | 18000.00 | 18 | % |
| 43 | TOWER C GROUND FLOOR ROAD WORK LABOUR FOR QUARRY DUST (SQFT) | 3,657.80 | SQFT | 2.25 | 8230.05 | 18 | % |
| 44 | TOWER C GROUND FLOOR ROAD WORK LABOUR FOR TRIMIX (SQFT) | 3,657.80 | SQFT | 9.00 | 32920.20 | 18 | % |
| 45 | TOWER C GROUND FLOOR ROAD WORK LABOUR FOR WMM (SQFT) | 7,315.60 | SQFT | 18.00 | 131680.80 | 18 | % |
| 46 | TOWER C GROUND FLOOR ROAD WORK LABOUR FOR WMM (SQFT) | 2,000.00 | SQFT | 18.00 | 36000.00 | 18 | % |
| 47 | TOWER C GROUND FLOOR ROAD WORK LABOR FOR EXCAVATION (SQFT) | 3,657.80 | SQFT | 6.00 | 21946.80 | 18 | % |
| 48 | TOWER C GROUND FLOOR ROAD WORK LABOR FOR GROOVE CUTTING WITH BITUMEN FILLING (SQFT) | 3,657.80 | SQFT | 1.75 | 6401.15 | 18 | % |
| 49 | TOWER C GROUND FLOOR ROAD WORK LABOR FOR PCC (SQFT) | 3,657.80 | SQFT | 4.00 | 14631.20 | 18 | % |
| 50 | TOWER C GROUND FLOOR ROAD WORK LABOR FOR STEEL BINDING (SQFT) | 3,657.80 | SQFT | 2.10 | 7681.38 | 18 | % |

We have pleasure in placing with you our Work order for the following contract kindly execute the work as per the instruction given by our site incharge.

| | | | | | | | | |
|---|---------------------------------------|----------|------|-------|-----------|----|---|--|
| 51 | COMMON ROAD WORK | | | | | | | |
| | LABOUR FOR WMM (SQFT) | 7,618.40 | SQFT | 18.00 | 137131.20 | 18 | % | |
| <p>Spc. WMM : Layer-1. Big Metal WMM (WET MIX MACADAM) 100 mm thick(compact) 'VIBRO-COMPACTED' Layer. Shall be done on existing ready laye without any change if gradient Laying WMM in a thickness of 125 mm in proper line, level, grade and camber, compacting the same with vibro-roller etc. complete. Labour name LABOUR FOR WMM</p> <p>WMM : Layer-2. Laying WMM in a thickness of 125 mm in proper line, level, grade and camber, compacting the same with vibro-roller etc. complete. INFRA Labour name LABOUR FOR WMM</p> | | | | | | | | |
| 52 | COMMON ROAD WORK | | | | | | | |
| | LABOUR FOR TRIMIX (SQFT) | 3,809.20 | SQFT | 9.00 | 34282.80 | 18 | % | |
| <p>Spc. RCC/PCC 125 mm thick with SYSTEM 'TRIMIX' RMC free supply by customer Fixing ISMC Channels in required line and level for side shuttering and guide for double beam surface vibrator to construct 125 mm thick PCC floor on prepared and fairly leveled sub-base in required levels. Laying PCC for floor concrete in a thickness of 125 mm and level precisely by using double beam surface (screed) vibrator. The leveled concrete shall be finished by using 'TRIMIX' system of power floating and power trowelling, making palas for clients to cure for 07 days.etc. Labour name LABOUR FOR TRIMIX (SQFT)</p> | | | | | | | | |
| 53 | COMMON ROAD WORK | | | | | | | |
| | LABOUR FOR QUARRY DUST (SQFT) | 3,809.20 | SQFT | 2.25 | 8570.70 | 18 | % | |
| <p>Spc. Laying Quarry Dust in proper line, level, grade and camber, compacting the same with vibro-roller etc. Labour name LABOUR FOR QUARRY DUST</p> | | | | | | | | |
| 54 | COMMON ROAD WORK | | | | | | | |
| | LABOR FOR STEEL BINDING (SQFT) | 3,809.20 | SQFT | 2.10 | 7999.32 | 18 | % | |
| <p>Spc. Reinforcement of 8mm steel 300mm c/c with free steel supplied by customer Labour name LABOR FOR STEEL BINDING</p> | | | | | | | | |
| 55 | COMMON ROAD WORK | | | | | | | |
| | LABOUR FOR PCC (SQFT) | 3,809.20 | SQFT | 4.00 | 15236.80 | 18 | % | |
| <p>Spc. PCC 100mm with free supply of RMC at site LABOR FOR PCC (SQFT)</p> | | | | | | | | |

We have pleasure in placing with you our Work order for the following contract kindly execute the work as per the instruction given by our site incharge.

| | | | | | | | | |
|----|---|----------|------|------|---------|----|---|--|
| 56 | COMMON ROAD WORK | | | | | | | |
| | LABOR FOR GROOVE CUTTING WITH BITUMEN FILLING (SQFT) | 3,809.20 | SQFT | 1.75 | 6666.10 | 18 | % | |

Spc. Groove Cutting with 'Diamond-Blade Cutter' for controlling effect of temperature stresses on concrete road with bitumen filling
Labour name LABOR FOR GROOVE CUTTING WITH SQFT

| | | | | | | | | |
|----|------------------------------------|----------|------|------|----------|----|---|--|
| 57 | COMMON ROAD WORK | | | | | | | |
| | LABOR FOR EXCAVATION (SQFT) | 3,809.20 | SQFT | 6.00 | 22855.20 | 18 | % | |

Spc. Earthwork - Excavation, Mobilisation and Filling work with Jcb, tractors at site upto 150mm thickness. (excess thickness shall be charged proportionately).
Dressing & Levelling of Earth with Labour or required means
Labour name LABOR FOR EXCAVATION (SQFT)

| | | |
|--|----------------------------|-------------------|
| | Contract Amount (A) | 1479562.40 |
| | Total GST (B) | 266321.20 |
| | Total (A + B) | 1745883.60 |

Terms & Conditions

SAFETY TERMS

- 1) Work Compensation (WC) Policy is a must for every contractor.
- 2) Required all their laborers Aadhar card copy and Passport size Photo.
- 3) All PPES in Contractor Scope.
- 4) TPI (Third Party Inspection) Certificate must for their Machineries which they install on our site.
- 5) Every Quarterly they must submit a service report of their respective machines to the site incharge.
- 6) Contractor has to maintain enough lighting during night work at site.
- 7) Debit Note Policy will be applicable if the contractor failed to maintain the safety norms

* All responsibilities of goods during transportation and unloading at site by supplier and vendors.

* Please submit your Bill/invoice along with delivery challan and PO copy in favour of Neptune Realty Pvt. Ltd. At project site office officialy.

* Billing amount should not exceed the rate and total value mentioned in this WO.

* Failure to comply with specification, terms and conditions of this order or accepted delivery. schedule shall be sufficient grounds for cancellation of order by purchase with out being liable.

For NEPTUNE REALTY PVT. LTD.

Authorized Signatory