



NEPTUNE CAMPUS, NEAR ATLANTIS HEIGHTS, DR.VIKRAM SARABHAI MARG, VADIWADI, VADODARA,GUJARAT, 390007

Ph.No. : 0265-2350630/39 Website : www.neptunerealtygroup.com

## WORK ORDER

WO No.	170	SHIP TO:	
WO Date:	01/09/2022	NEPTUNE REALTY PVT. LTD.	
Contractor Name	<b>Star Engineering</b>	NEPTUNE TRION EXP	
Address:	49,/vaikund complex, Near water tank, rangoli GIDC Vadodara.	NEPTUNE CAMPUS, NR. ATLANTIS HEIGHTS, GORWA ROAD, VADODARA	
Contact No	9724273443	WO Title	
PAN :	ASOPG4902B		
GST :		GST No: 24AAACN9837D1ZI	Gujarat

We have pleasure in placing with you our Work order for the following contract kindly execute the work as per the instruction given by our site incharge.

Sr.No	Item Description	Qty	Unit	Rate Rs.	Amount	GST %
1	TOWER A GROUND FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0 %
2	TOWER A 1ST FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0 %
3	TOWER A 2ND FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0 %
4	TOWER A 3RD FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0 %
5	TOWER A 4TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0 %
6	TOWER A 5TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0 %
7	TOWER A 6TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0 %
8	TOWER A 7TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0 %
9	TOWER A 8TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0 %
10	TOWER A 9TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0 %
11	TOWER A 10TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0 %

We have pleasure in placing with you our Work order for the following contract kindly execute the work as per the instruction given by our site incharge.

12	TOWER A 11TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
13	TOWER A 12TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
14	TOWER A 13TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
15	TOWER A 14TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
16	TOWER A 15TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
17	TOWER A 16TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
18	TOWER A 17TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
19	TOWER C GROUND FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
20	TOWER C 1ST FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
21	TOWER C 2ND FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
22	TOWER C 3RD FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
23	TOWER C 4TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
24	TOWER C 5TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
25	TOWER C 6TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
26	TOWER C 7TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
27	TOWER C 8TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
28	TOWER C 9TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
29	TOWER C 10TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%

We have pleasure in placing with you our Work order for the following contract kindly execute the work as per the instruction given by our site incharge.

30	TOWER C 11TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
31	TOWER C 12TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
32	TOWER C 13TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
33	TOWER C 14TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
34	TOWER C 15TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
35	TOWER C 16TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
36	TOWER C 17TH FLOOR DUCT FABRICATION WORK LABOR FOR FABRICATED DOOR (NOS)	1.00	NOS	5300.00	5300.00	0	%
Spc. For Material Hoist Opening							

Contract Amount (A)	190800.00
Total GST (B)	0.00
Total (A + B )	190800.00

**Terms & Conditions**

**SAFETY TERMS**

- 1) Work Compensation (WC) Policy is a must for every contractor.
- 2) Required all their laborers Aadhar card copy and Passport size Photo.
- 3) All PPES in Contractor Scope.
- 4) TPI (Third Party Inspection) Certificate must for their Machineries which they install on our site.
- 5) Every Quarterly they must submit a service report of their respective machines to the site incharge.
- 6) Contractor has to maintain enough lighting during night work at site.
- 7) Debit Note Policy will be applicable if the contractor failed to maintain the safety norms

- \* All responsibilities of goods during transportation and unloading at site by supplier and vendors.
- \* Please submit your Bill/invoice along with delivery challan and PO copy in favour of Neptune Realty Pvt. Ltd. At project site office officialy.
- \* Biling amount should not exceed the rate and total value mentioned in this WO.
- \* Failure to comply with specification, terms and conditions of this order or accepted delivery. schedule shall be sufficient grounds for cancellation of order by purchase with out being liable.

For NEPTUNE REALTY PVT. LTD.

\_\_\_\_\_  
Authorized Signatory